

Quotation for Electrical work at OLD LIBRARY MUSEUM FIRST FLOOR .

BOQ

Sr. No.	DESCRIPTIPON	Qty	UNIT	RATE	AMOUNT
1	Supply , Installation , Testing and Commisionig of ETPN DB IP43IK09 with metal door 12 way Db	1	Set		
	40 AMP 4P MCB outgoing 1 no.				
	40 AMP 2P 100mA RCBO outgoing 3 no.				
	6/32 AMP SP MCB outgoing 30 NO.				
2	Supply , Installation , Testing and Commisionig of Power Point wiring with 25 x 16mm casing and caping precision make and 3No 2.5 Sq.mm FRLS wire, polycab make for 6/16 Amp Socket	6	Set		
3	Supply , Installation , Testing and Commisionig of Power Point wiring with 25 x 16mm casing and caping, precision make and 2 No 4 Sq.mm & 1 no 2.5 sq.mm FRLS wire, Polycab make for A/C Point	3	Nos		
4	Supply , Installation , Testing and Commisionig of Light point and Fan Point wiring with 25 x 16mm casing and caping, Precision make and 3 No 1.5 Sq.mm CU FRLS wire, polycab make including 3 plate celling rose and all other accessories for Light & Fan Point Wiring	28	Nos		
5	Supply , Installation , Testing and Commisionig of 2 no 6/16 Amp socket, 2 nos 16 amp switch ,6 Module box with plate complete with all accessories (North west Make- Nowa series)	6	Nos		
6	Supply , Installation , Testing and Commisionig of 6 Amp 1 way switch - 3 No & 120 Watt Fan regulator - 3 No with 9 Module box with front plate complete with all accessories (North west Make-nowa series)	3	Set		
7	Supply , Installation , Testing and Commisionig of AC enclosure box with 32 amp 3 pin socket and box + 32 Amp SP MCB complete with all accessories, Legrand Make	3	Nos		
8	Supply , Laying 1100 V XLPE 4C X 16 Sq. mm. Copper Cable, Polycab make And 2 no 12 swg copper earthing complete with all accessories HIMALAYA New LT Panel to Old Library New DB	40	Mtr		
9	Supply , Installation 4C x 16 Sq. mm. Copper Armoured Cable end termination with gland ,lugs & all accessories	2	Set		
10	Supply , Installation , Testing and Commisionig of light fitting 1 x 28 watt T5 fluroscent suspended (max 1.5m) similar to wipro S4VIOURW/F20128 make complete with all accessories	19	Nos		
11	Removing old wiring ,fitting ,celling fan	1	Job		
TOTAL					0